BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18666/CALL-3

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements of Roads from Amruthahalli Halumanthappa house to Muninagappa House in Ward No .7, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of RAKESH H M		
				In Figures		In Words
1	470	KSRRB 300-47 Scarifying Kankar /gravel/ metal crust upto 150mm thick with power roller and scarifier , disposal of stuff including cost of labour charges HOM of machinaries MORTH Specification No. 305.4.3 (P-146, Item No. 19.53 SR 2015-16)	sqm	25.92	12182.40	Rupees Twenty Five and Ninety Two Paise Only
2	32.4	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	cum	83.16	2694.38	Rupees Eighty Three and Sixteen Paise Only
3	470	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (148, I.No. 19.64) 2015-16	sqm	4.86	2284.20	Rupees Four and Eighty Six Paise Only
4	38.08	KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.3) SR-2015-16	cum	5070.6	193088.45	Rupees Five Thousand Seventy and Sixty Paise Only
5	120	KSRB5 25 providing and constructing non load bearing with cement concreate solid blocks with compresive strenth not less than 3.5 newtown per sqmm with cement mortor 1:4 with block of size 40X20 X20cms (lXbXh) conforming to is:2185/1965 in superstructure including the cost of materials labour charges , scaffolding curing complete as specification (P.No.25 I.No.5.27 of PW,P&IWTD S.R 2015-16	sqm	1018.44	122212.80	Rupees One Thousand Eighteen and Forty Four Paise Only
6	59.08	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.48 SR-2015-16	cum	6332.04	374096.92	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
7	470	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P. 174 I. No. 22.7) SR-2015-16	sqm	97.2	45684.00	Rupees Ninety Seven and Twenty Paise Only
8	37.5	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(P. 172 I. No. 22.8.1) SR-2015-16	Rmt	124.2	4657.50	Rupees One Hundred Twenty Four and Twenty Paise Only

16/5/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of RAKESH H M		
				In Figures		In Words
9	25.92	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2015-16	cum	192.24	4982.86	Rupees One Hundred Ninety Two and Twenty Four Paise Only
10	4.32	KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.3) SR-2015-16	cum	5070.6	21904.99	Rupees Five Thousand Seventy and Sixty Paise Only
11	11.52	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2015-16	cum	4135.0	47635.20	Rupees Four Thousand One Hundred Thirty Five Only
12	16.78	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P 15, I.No 4.28) SR-2015-16	cum	244.08	4095.66	Rupees Two Hundred Forty Four and Eight Paise Only
13	8.64	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.48 SR 2015-.16	sqm	6332.04	54708.83	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
14	1.34	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17, I.No. 4.46.2) SR-2015-16	qtl	69805.8	93539.77	Rupees Sixty Nine Thousand Eight Hundred Five and Eighty Paise Only
15	67.2	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.112.I.No. 15.3) SR-2015-16	sqm	99.36	6676.99	Rupees Ninety Nine and Thirty Six Paise Only
16	58.32	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	72.71	4240.45	Rupees Seventy Two and Seventy One Paise Only
					994685.41	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/5/16

16/05